HESSARGHATTA WATER SUPPLY DIVISION.

ADVERTISEMENT.

The 19th September 1894.

Tenders are hereby invited for construction of two head sluices at Hessarghatta Tank in connection with Hessarghatta Water Supply Project.

2. The plans, estimates, and specifications may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer by the end of September 1894.

4. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 100 as earnest money.

6. Within eight days of the acceptance of the tender, the contractor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. Work to be completed by end of December 1894.

Tenders for construction of two head sluices at Hessarghatta tank in connection with Hessarghatta Water Supply Project.

Items of Work.	Per.	Rate.	Quantity.	Cost.
Earthwork excavation	C. Yd.		512	
Concrete in surki	C. Ft.		5,090	
Burnt stone in surki mortar (foundation)	Do		3,082	
Cut-stone ditto ditto	Do		892	
Stone in surki mortar (superstructure)	Do		9,298	
Pointing with chunam	Sqr.		34·80	
Dressed quoins	S. Ft.		1,666	
Plastering with surki	Sqr.		30·60	
Burnt stone slabs, dressed (6″)	S. Ft.		1,446	
Rough stone work	C. Yd.		150	
Shutter and gear, &c., complete	No.		6	
Burnt stone slabs, dressed (3″)	S. Ft.		560	
Archwork of shaped brick in surki mortar, first class, including centering	C. Ft.		3,124	
Teak wood beams bolted down to face wall to carry screw gearing	Do		20	
Cut-stone caps to pedestals and cut-water	Each.		12	

R. T. SCALDWELL,
Executive Engineer.

TUMKUR DISTRICT.

NOTICE.

The 18th September 1894.

The depositors of the Mysore Government Savings Bank, Tumkur District, are hereby requested to send their Pass Books to the Tumkur District Treasury, for annual adjustment of interest for the year 1893-94.

B. J. KUMARASWAMI NAIK, *Treasury Officer.*